BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/06/2014-15 Dated: 23-01-2015

APPROVED TENDER SCHEDULE –'B'

Item No: 11

Name of Work:-:Reconstruction of Anganawadi building in 3rd phase in ward No:04

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri N LOKANATHREDDY	
				Rate	Rate in Words
1	Dismantling size stone masonry in cement mortor and stacking the size stone within a radious of 50 m and removing the debries to a distance up to 200m etc as per specifivations and directions of the engineer in charge of the work	Cum	18.97	163.00	Rupees one hundred sixty three only
2	Dismantling burnt brick masonry in Cement/lime/clay mortor and stacking the bricks within aradious of 50m and removing the debries to adistance up to 200m etc. and per specifications and directions of the engineer incharge of the work	Cum	27.06	148.00	Rupees one hundred forty eight only
3		Cum	20.70	150.00	Rupees one hundred fifty only
4	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m. In depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead uplo 50m. after breaking of clods complete as per specifications. Specification. No. KBS 2.1(b) / 2.3.5 **PWD SR 2014-15(P.5/2.4)**	Cum	76.46	271.00	Rupees two hundred seventy one only
5	KSRB 2.10: Providing sand cement bed with 5% cement with all leads for all materials and lift of 1.5 m. machine mixed, laid in layers of 15cms. thick and well compacted for foundation, including curing cost of materials labour and HOM complete as per specifications. specification. No. KBS (P.6/I.2.17 PW, P & IWTD -SR 2014-15	Cum	5.72	3012.00	Rupees three thousand twelve only
6	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix **1:4:8** using **40mm** and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 **PWD SR 2014-15 (P.12/4.3)**	Cum	18.44	4971.00	Rupees four thousand nine hundred seventy one only
7	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (P.25/I.5.6	Cum	21.97	3934.00	Rupees three thousand nine hundred thirty four only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri N LOKANATHREDDY	
				Rate	Rate in Words
8	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in **basement** with **cement mortar 1:6**, edges of stone chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specification. KBS 5.1.13 **(P.23/5.9) PWD SR 2014-15**	Cum	5.78	4658.00	Rupees four thousand six hundred fifty eight only
9	KSRB 15.1.3: Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. **Page No. 109/ Item No. 15.3 / PWD SR 2014-15**	Sqm	10.40	95.00	Rupees ninety five
10	KSRB 4-1.6 : Providing and laying in position plain cement concrete of nominal mix 1:2:4 using 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/I.4.6 PW, P & IWTD -SR 2013-14)	Cum	10.18	5464.00	Rupees five thousand four hundred sixty four only
11	KSRB 2.3: Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. specification. No. KBS 2.9 (P.6/I.2.10 PW, P & IWTD -	Cum	76.46	121.00	Rupees one hundred twenty one only
12	KSRB 4.2.2: Providing and laying in position reinforced cement concrete of mix 1:1.5:3 with **20mm (M20)** and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for ground floor level for roof slabs, starecase, lintel, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, coping, bed struts, buttersses, string or lacing courses, parapets, coping, bed blocks, plain window cils, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No.KBS 4.1, 4.6 **(P.No.13/4.11) PWD SR 2014-15**	Cum	27.64	6220.00	Rupees six thousand two hundred twenty only
13	KSRB 4.9.2 : Providing T.M.T Steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required , tying with binding wire and anchoring to the adjoining memebers wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 **PWD SR 2014-15(P.NO17/4.46)**	Cum	27.41	8108.00	Rupees eight thousand one hundred eight only
14	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (P.16/I.4.28 PW, P & IWTD	Sqm	15.84	242.00	Rupees two hundred forty two only
15	KSRB 4-6.5: Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. Specification No. KBS 4.6.2 (P.17/I.4.32 PW, P & IWTD	Sqm	66.00	374.00	Rupees three hundred seventy four only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri N LOKANATHREDDY	
				Rate	Rate in Words
16	KSRB 4-6.7 :Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (P.17/I.4.34 PW, P & IWTD -	Sqm	77.64	266.00	Rupees two hundred sixty six only
17	KSRB 4-6.2: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (P.16/I.4.29 PW, P & IWTD	Sqm	69.63	587.00	Rupees five hundred eighty seven only
18	KSRB 4.2.10 : Providing and laying in position reinforced cement concrete of nominal mix 1:1.5:3 with 12mm and down size graded granite metal, machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications. Specification No. KBS 4.1, 4.6 (P.13/I.4.19 PW, P & IWTD -SR 2013-14)	Sqm	3.92	469.00	Rupees four hundred sixty nine only
19	KSRB 4-6.10 :Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc., including edges including cost of all materials, labour complete as per specification. Specification No. KBS 4.6.2 (P.17/I.4.37 PW, P & IWTD	Sqm	3.92	276.00	Rupees two hundred seventy six only
20	KSRB 5-14: Providing and constructing precast concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1955 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P.27/I.5.27 PW, P & IWTD -	Sqm	149.30	1019.00	Rupees one thousand nineteen only
21	Providing and fixing RCC Slabs 5cms thick for wall shelves with 12mm and down size jelly cement concrete 1:1 1/2 :3 including CM 1:3 plaster finishing, curing etc., complete (excluding the cost of steel, fabrication and plastering charges).P 18 / 4.57.	Sqm	56.94	570.00	Rupees five hundred seventy only
22	KSRB 7.9: Providing and fixing M.S. Grill work for windows and ventilators weighing 21kg/sqm using M.S Flats or M.S. Square roads, or combination of M.S. flats and quare roads as per approved design drawing including cutting steel sections etc as per specifications.	kgs	235.20	103.00	Rupees one hundred three only
23	KSRB 9.4-2 : Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications. Specification No. KBS 9.33 (P.56/I.9.11 PW, P & IWTD -	Cum	0.55	110720.00	Rupees one lakh ten thousand seven hundred twenty only
24	KSRB 9.5-2 : Providing and fixing in position fully paneled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) Specification No. KBS 9.34 (P.57/I.9.15 PW, P & IWTD	Sqm	11.97	4842.00	Rupees four thousand eight hundred forty two only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor / Approved Rates / Sri N LOKANATHREDDY	
				Rate	Rate in Words
25	KSRB 9-16.2 : Providing and fixing in position Honne wood fully paneled shutters for windows with styles and rails of 35mm. thick, 75mm wide in two halves with panels of 25mm thick including cost of materials, labour charges, HOM of machineries complete as per specifications. (excluding cost of fixtures). Specification No. KBS 9.34 (P.48/I.9.44 PW, P & IWTD --SR 2014-15)	Sqm	4.32	5105.00	Rupees five thousand one hundre five only
26	KSRB 7.7 : Providing and fixing in position in cement concrete 1:3:6 steel glazed windows and ventilators side hung/top hung fully openable as per approved drawings using Z angles of 25x33x3mm, weighing 1.419 Kg/m both for outer and inner frames and central mullion section of size 25x46x3mm, weighing 2.28Kg/m duly providing T section 19x19x3mm weighing 0.839 kg/m for glazing of windows not more than 34 cms. c to c including providing and fixing 4mm. thick reeded glass with teakwood beading of required size, all steel sections should confirm to I.S 7452:1990, 4 Nos. of hold fasts of approved size, section should be cut to length welded and electrically grinded subdividing frames of unit shall be tenonned and revetted into the frames electrically. All the steel surface shall be throughly cleaned free of rust and painted with one coat of anti-corosive paint and finishing with two coats of ready mix paint of approved colour and make including cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Specification No. KBS 7.12.1 / 7.12.2 / 7.12.3 / 7.12 (P.37/I.7.7 PW, P & IWTD -	Sqm	0.54	3447.00	Rupees three thousand four hundre forty seven only
27	KSRB 9-27.1 : Fixing of door frame in an existing opening including embedding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debris with lead upto 50 m. including cost of materials, labour charges, complete as per specifications. (P.62/I.9.80 PW, P & IWTD -SR 2013-14)	Nos	6.00	1065.00	Rupees one thousand sixty five onl
28	KSRB 9-27.2 : Fixing of window frame in an existing opening including embedding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debris with lead upto 50 m. including cost of materials, labour charges, complete as per specifications. (P.62/I.9.81 PW, P & IWTD -SR	Nos	4.00	721.00	Rupees seven hundred twenty one only
29	KSRB 15-3-13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (P.123/I.15.21 PW, P & IWTD	Sqm	60.99	191.00	Rupees one hundred ninety one only
30	KSRB 15-3.7 : Providing 18mm thick cement plastering single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (P.122/I.15.15 PW, P & IWTD -SR 2013-14)	Sqm	162.81	243.00	Rupees two hundred forty three only
	KSRB 15-7 : Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications. (P.124/I.15.33 PW, P & IWTD -	Sqm	223.80	22.00	Rupees twenty two only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri N LOKANATHREDDY	
				Rate	Rate in Words
32	KSRB 15-3.10 : Providing 20mm thick cement plaster in single coat with cement mortar 1:3, to stone masonry including rounding off corners wherever required smooth rendering. : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (P.123/I.15.18 PW, P & IWTD	Sqm	199.60	260.00	Rupees two hundred sixty only
33	Providing and laying flooring using prepolished, water cut / gang saw 19mm thick using grey granite laid over existing floor in CM 1:4 at 20mm thick (average) and pointed with white / grey pigment etc., complete (P.117/I.14.47.1 PW, P & IWTD -	Sqm	46.46	2767.00	Rupees two thousand seven hundred sixty seven only
34	KSRB 15-15.1: Providing and applying painting in two coats with plastic emulsion paint with primer of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. - with primer (P.126/I.15.51.2 PW, P & IWTD -	Sqm	223.80	63.60	Rupees sixty three and paise sixty only
35	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint with primer of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. - with primer (P.127/I.15.53.2 PW, P & IWTD -SR 2014-15	Sqm	199.60	79.50	Rupees seventy nine and paise fifty only
36	KSRB 15-17.6: Providing and applying painting two coats (excluding priming coat) on new wood surface and/or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications. (P.128/I.15.60.1 PW, P & IWTD -SR 2014-15	Sqm	37.87	82.68	Rupees eighty two and paise sixty eight only
37	KSRB 8.6-5 : Providing and fixing on wall surface 2.5 kg / sq.cm H.D.P.E. rain down water pipes 90 mm outer dia approved make and brand with necessary specials like shoes, bends and offsets fixed with iron clamps, wall plugs, screws, including cost of materials, labour, curing complete as per specifications. (P.52/I.8.16 PW, P & IWTD -SR 2014-15	Mtr	12.00	418.70	Rupees four hundred eighteen and paise seventy only
38	KSRB 14.14-2: Providing colour glazed tiles all sizes 10mm thick for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing using white cement with matching colour pigment, including cost of materials, labour, curing, complete as per specifications. Specification No. KBS 14.15.2 (P.93/I.14.33 PW, P & IWTD -SR SR 2014-15	Sqm	17.01	850.00	Rupees eight hundred fifty only
39	Providing flooring with 60 cms.x 60 cms. size Vitrified glazed tiles of approved quality & make, fixed on top of existing flooring fixed with suitable adhesive, including cutting the tiles to the required size and fixing etc., complete. (P.94/I.14.44 PW, P & IWTD SR 2014-15	Sqm	2.34	1100.00	Rupees one thousand one hundred only
40	Providing and fixing to wall, ceiling and floor high density polyethelene pipes 6.00 Kgf/sq.cm working pressure 110mm outside diameter with special flange compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications -SR 2014-15	Mtr	20.00	610.00	Rupees six hundred ten only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri N LOKANATHREDDY	
				Rate	Rate in Words
41	KSRB 13-6.1-1 : Providing and fixing in position brass bib cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.2 / 13.3 (P.80/I.13.23 PW, P & IWTD	Each	2.00	250.00	Rupees two hundred fifty only
42	KSRB 11-1: Providing and fixing white vitreous china clay, water closet Indian type (Squatting pan) of size 580mm with footrests, 100mm S or P trap, 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 32mm diameter flush pipe fittings and clamps, overflow arrangements with specials and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11 (P.67/I.12.1 PW, P & IWTD	Each	2.00	3500.00	Rupees three thousand six hundred only
43	KSRB 13-11.1: Providing and placing on terrace, polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. (For 1000 litre capacity). Specification No. KBS 13.22 (P.83/I.13.78 PW, P & IWTD	Nos	1.00	8900.00	Rupees eight thousand nine hundred only
44	KSRB 13-1.3: Providing and fixing to wall, ceiling and floor galvanised / mild steel tube 25mm dia nominal bore with fittings (medium grade weight 2.51kg/ mtr) B class including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification	Mtr	15.00	325.00	Rupees three hundred twenty five only
45	KSRB7 7.1 Providing and fixing in position colap sablesteel shtters with single or double leleaf with vertical channel 120m mx20mmx2mm braced with flat iron diagonals 20mmx5mm size, wh top and bottom rails of T iron sections of 40x40x6mm with 38mm dia steel pulleys complete with bllt and nuts locking arrangements stopers handles on borht sides with 7.5 cms opeinings at 10 cms C to C applying a priming coat of red lead paint cost of materials, labour HOM of machinery complete as pe rspecifications	Sqm	6.84	4600.00	Rupees four thousand six hundred only
46	Providing and fixing 2 HP Pump Motor	Nos	1.00	10000.00	Rupees ten thousand only
47	Supplying and wiring adoptiong loop system in existing PVC conduit /casing caping using copper PVC insulated multi strand 2x1.5Sqmm copper wire with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet/gang box, the other end of the wires shall be terminated with sufficient loose legnth in a wood/PVC round block, complete for each outlet. (P.4/I.8.I.C) Electrical-SR 2012-13)				
	b) Medium point above 3Mtr upto 6Mtr from tapping point to out let via switch	Each	2.00	180.00	Rupees one hundred eighty only
	c) Long point above 6Mtr upto 10Mtr from tapping point to out let via switch		1.00	380.00	Rupees three hundred eighty only
48	Supplying 6A flush /projected type socket and a 6 amps flush/projected type SP switch either surface mounting in a gang box or in a 4mm thick plastic sheet and fixing over a flush mounted wooden box and wiring using necessary capacity wires as required. (P.6/I.12a) Electrical -SR 2012-13)	Each	4.00	100.00	Rupees one hundred only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri N LOKANATHREDDY	
				Rate	Rate in Words
49	Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, necessary masonry patch work complete. (P.4/I.6) Electrical - SR 2012-13)	Each			
	a) 4"x4"x3"		2.00	88.00	Rupees eighty eight only
	b) 12"x12"x3"		1.00	98.00	Rupees ninety eight only
	c) 10"x7"x3"		2.00	80.00	Rupees eighty only
50	Supplying 4mm thick plastic sheet with necessary nitches for fixing switches regulated etc.., and fixing on existing wooden or metal box using N.F. screws.., (P.10/I.22) Electrical SR - -SR 2012-13)	S.Cm	60.00	0.30	paise thirty only
51	Extra for groove cutting, plastering and colour washing for embedding PVC conduit/GI pipe and plastering finishing the wall uplo wall surface complete upto 50mm conduit in brick in wall (P.3/I.7a) Electrical-SR 2012-13)	Rmtr	60.00	20.00	Rupees twenty only
52	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit..... The pit should be filled with equal proportion of salt and charcoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc, is to be established through GI wire of size as per IS1 specification 7.3.3 of IS 732 using 12 mm dia bolts, nuts, washers and checknuts etc, the pipe shall have 16 through holes of 122 mm dia. (P.68/I.2) Electrical -SR 2012-13)	Each	1.00	3000.00	Rupees three thousand only
53	Supplying and fixing of porcelain fuse chanel with cut out on existing wooden/panel using ncessary nuts, bolts and washers etc complete (P.32/I.3a) Electrical -SR 2012-13)	Each	2.00	60.00	Rupees sixty only
54	Supplying 20mm dia 2mm thick heavy guage PVC conduit pipe with suitable size bends, metal junction boxes, adhesive paste etc and running before concreting the slabs. The conduit should be tied to the reinforcement roads by using binding wire and unused ways of junction boxes and pipe ends should be covered using PVC and enclosures and run with 18 SWG GI fish wire run throughout the conduit wherever necessary. (P.2/I.2a) Electrical SR - 2014-15	Rmtr	80.00	40.00	Rupees forty only
55	Supplying and fixing PBBC brass/Bakelite straight or slant batten holder and wiring, within 60W/230 Volts lamps. (P.13/I.12a) Electrical SR - 2014-15.	No.	4.00	70.00	Rupees seventy only
56	Supply patty type fluorescent tube light fitting of 4 feet 40 watts fluorescent tube of 230 volts made of M.S. sheet and stove enameled with heavy duty polyfill aluminum choke, starter, locking type brass contact holders mounted on foldable type sheet base fully wired.for use on 230 volts AC supply including 1 Nos 4'-36/40 watts fluorecent tube A Group (P.16/I.2a) Electrical SR - 2014-15	No	4.00	450.00	Rupees four hundred fifty only
57	Wiring for lighting / power circute using one of PVC insulated 1100v/grade multies and copper conductor single core cable in open or consealed system of wiring A Group materials 1.50 Sqmm materials (P.9/I.20Ib) Electrical SR - 2014-15	Rmtr	55.00	20.00	Rupees twenty only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri N LOKANATHREDDY	
				Rate	Rate in Words
58	Supplying and running of GI / Copper conductor for grounding & (along with other wires of CTS or conduit system of wiring) using if necessary suitable size clamps bolts nuts and washers etc. (P.68/I.3Ic) Electrical SR - 2014-15 c) 40X6mm	Rmtr	12.00	230.00	Rupees two hundred thirty only
59	Supplying and fixing miniature circuit breakers/Isolators on existing MCB distribution boards using necessary fixing materials and wiring complete as required (P.36/I.12Ba) Electrical SR - 2014-15	No.	4.00	380.00	Rupees three hundred eighty only
60	Supplying capacitor type ceiling fan complete with down rod blades, shakle, regulator canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system and as per technical data approved (Almanord, Unique ISI, Anchor, Crompton, Khaitan, Bajaj, Usha, Johnson make) (P.23/I.23IIa) Electrical SR - 2014-15	Nos	4.00	1950.00	Rupees one thousand nine hundred fifty only
61	Fixing a ceiling fan of all capacities and all types to the existing S hook with fan regulator to the existing board together with supplying and fixing a 5 ampers ceiling rose, necessary length of 23/0.0076 inch PVC insulated twin twisted copper wire and wiring completely. (P.29/I.8) Electrical SR - 2014-15	Nos	4.00	120.00	Rupees one hundred twenty only
62	Supplying and fixing 32mm dia class A GI pipe bracket upto 2 mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 watts fluoroscent tube street light fitting of all capacities to GI or CI or rail or RCC pole/wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires complete. (P.28/I.12b) Electrical SR-2014-15	Nos	4.00	700.00	Rupees seven hundred only
63	Digging of trench of 0.6m deep x 0.50mtr wide refiling the trench to the required ground level and consolidating etc., complete. In Hard Soil (P.70/I.6b) Electrical SR - 2014-15	Rmtr	6.00	60.00	Rupees sixty only

Signature of the Contractor

N. Lokanath reddy

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.